



# RailTel Corporation of India Limited

*A Government of India (Ministry of Railways) Undertaking*

Southern Region Head Quarters, Second Floor, B-Block, Rail Nilayam, Secunderabad-500071 (AP)

visit [www.railtelindia.com](http://www.railtelindia.com), Tel: 040-27821134 Fax: 27820682,

Corp & Regd Office: Plot no 143, Institutional Area, Sector-44, Gurgaon-122003

## CORRIGENDUM-I

Dt.24.01.2022


Sub: Patch Replacement work – Ernakulum Territory.

Ref: RCIL-ETender-21-22-ERS-32, Dt.21.01.2022.

\*\*\*\*

With reference to the above tender, Corrigendum-I is issued herewith, for the "SCHEDULE OF WORK" as Per Annexure-I" (Refer : Section I, Chapter-I, page no.15-16 of tender document)

All other terms and conditions of EOI remain the same.

  
24/01/2022

Joint General Manager/Projects/SR  
for RailTel Corporation of India Ltd

**SECTION I**  
**Chapter II**

**SCHEDULE OF REQUIREMENT**

Tender No: E-Tender No: RCIL-ETender-21-22-ERS-32

S.No	Description	Unit	Rate	Quantity			Total Qty (PGT+MDU +TVC)	Amount in Rs (Qty*Rate)	GST @ 18%	Total amount with GST
				PGT	MDU	TVC				
1	i) Trenching to a depth of 1.2 Meter and 300 mm wide and backfilling after OFC as per Specification Excavation of Trench in Normal and hard soil to a depth of 1.2 Mtr except hard rock. Trees and bushes has to be cleared for making way to trench. ii) Excavation of trench when Hard Rock is encountered at various depth and providing CC protection as specified iii) Cutting of metal /CC/Tar road as required	KM	70000	23	13	23	59	4130000	743400	4873400
2	i) Supply and fixing of GI pipe / DWC pipe /C-Channel on bridges, culverts and crossing etc., ii) Laying of OFC at track crossing road crossing, LC gates etc by Horizontal Bore method only. iii) Supply of joint enclosure and splicing of 24F OFC. iv) Casting,	KM	85000	23	13	23	59	5015000	902700	5917700

transporting and fixing of RCC Route markers at an interval of 50 M. v) Protection works like concreting with CC etc., vi) Provision of RCC loop and joint chambers. vii) laying of HDPE duct, backfilling & removal of debris, blowing of OFC, Splicing, termination, testing and Commissioning of entire link. viii) Submission of ABD i.e As build Drawing duly mapped with GPS after completion of entire work								
<b>Total Rupees Fifty four lakhs eighty seven thousand only (rounded off)</b>								<b>10791100</b>
<b>Contractor's quoted percentage (in figures &amp; words)</b> <b>Below/At Par/Above (Including GST @18%)</b>								<b>Shall be filled online in IREPS portal only</b>
<b>Grand Total Amount after contractor quoted percentage</b> <b>In figures &amp; words:</b>								